



4271 Airpark Dr. • Standish, MI 48658
Telephone (989) 718-3250
Fax (989) 718-3253

OLEN SWARTZ
Commissioner

DR. RONALD SCHWAB
Commissioner

KEN STAWOWY
Commissioner

BRAD STAUFFER
Managing Director
bstauffer@arenaccrc.org

**ARENAC COUNTY ROAD COMMISSION
AND
IOSCO COUNTY ROAD COMMISSION**

NOTICE TO BIDDERS

2023 Overband Crack Fill Fixed Price - Variable Scope Project

The Arenac County Road Commission will receive sealed bids until 10:00 a.m. (to be opened and read at that time) on Thursday, January 5, 2023, at their office located at 4271 Airpark Drive, Standish, Michigan 48658, for the 2023 Overband Crack Fill Fixed Price – Variable Scope Project.

All materials must meet the current Michigan Department of Transportation 2020 Standard Specifications for Construction.

Specifications and bid documents may be obtained by contacting the Arenac County Road Commission by phone at (989) 718-3250 or email BStauffer@Arenaccrc.org, and the Iosco County Road Commission can be directed to Bruce Bolen, Engineer-Manager at (989) 362-4433 or email bolenb@ioscoroads.org.

The Arenac County Road Commission Board and or Iosco County Road Commission Board reserves the right to accept or reject any or all bids, to waive any informalities in the bids and to make the award in any manner deemed in the best interest of the County of Arenac and or County of Iosco. Bid price may be extended for one (1) additional year by mutual consent of all parties.

Arenac County Road Commission Board

Ken Stawowy
Olen Swartz
Dr. Ronald Schwab

**Arenac County Road Commission
And
Iosco County Road Commission**

2023 Overband Crack Fill Fixed Price - Variable Scope Project

Bid Opening January 5, 2023 at 10:00 a.m.

At

**ARENAC COUNTY ROAD COMMISSION OFFICE
4271 Airpark Drive
Standish, MI 48658**

INSTRUCTION TO BIDDERS

All “Completed Mile” entries made on the bid proposal by the Bidder shall be hand written in ink.

The “Completed Mile”, as stated, will govern in determining the correct total of the Bid Proposal.

If a “Completed Mile” sum already entered by Bidder on the proposal is to be altered, it shall be crossed out in ink. The Bidder shall enter above or below it and initialed in ink the new “Completed Mile” sum on the line of the change each time the “Completed Mile” sum is altered.

The Bid Proposal shall be signed and the complete address of the Bidder given.

All bids must be submitted in sealed envelope bearing the name of the bidder and clearly marked. All bids must be submitted on the documentation provided in the bid package.

The Arenac County Road Commission Board and or Iosco County Road Commission Board reserves the right to accept or reject any or all bids, to waive any informalities in the bids and to make the award in any manner deemed in the best interest of the County of Arenac and or County of Iosco. Bid price may be extended for one (1) additional year by mutual consent of all parties.

NOTICE TO BIDDERS

DESCRIPTION OF WORK:

Work consists of treating cracks on hot mix asphalt (HMA) surfaces using an overband process in accordance with the requirements of Section 502 of the Michigan Department of Transportation 2020 Standard Specifications for Construction (delete section 502.04) and as modified herein.

PROGRESS SCHEDULE:

Work for Arenac County Road Commission can begin after May 1, 2023 through June 30, 2023 and or September 1, 2023 through October 30, 2023 and all work shall be completed October 30, 2023, or as directed by the Managing Director.

Work for Iosco County Road Commission can begin after May 1, 2023 and all work shall be completed June 17, 2023, or as directed by the Engineer-Manager.

The Contractor shall provide 72 hours' notice to Arenac County Road Commission and or Iosco County Road Commission prior to beginning work on any stretch of road.

MEASUREMENTS and PAYMENTS:

The unit price includes all work, labor, equipment, and materials necessary for preparing and filling the cracks using the overband method, providing the required documentations, and corrective work. The unit price shall also include all traffic control in accordance with the MMUTCD and these specifications.

The measurement will be by the centerline of the roadway to the hundredth of a mile. This will include the full width of the pavement surface from edge of asphalt to edge of asphalt.

The successful bidder for Arenac County Road Commission will be determined by the most completed miles at the fixed price of \$85,000.00.

The successful bidder for Iosco County Road Commission will be determined by the most completed miles at the fixed price of \$175,000.00.

The successful bidder will invoice Arenac County Road Commission for the work performed in Arenac County and invoice Iosco County Road Commission for the work performed in Iosco County.

Overband Crack Fill completed work will be paid as the following, determined by dividing the fixed construction cost amount by the Contractor's total completed mile bid quantity which will be paid by the following unit price "Completed Mile".

CONTRACT PROVISION:

The Arenac County Road Commission and or Iosco County Road Commission reserves the right to cancel any of the lane miles and/or add lane miles to the contract. Any such cancellations or additions shall not change the "Completed Mile" unit price bid and the "Completed Mile" unit price shall remain firm until completion of the contract.

The Arenac County Road Commission and or Iosco County Road Commission may reject proposal, waive irregularities, advertise for new proposals, or proceed to do the work in other ways as it determines to be in the best interest. These actions will not entitle bidders to payment for cost of preparation of the proposal or the proposal or anticipated profits.

The bid may be extended by the Arenac County Road Commission and or Iosco County Road Commission for one (1) additional year with mutual agreement by all parties, the extension shall be based on "Completed Mile" unit price.

The Arenac County Road Commission and Iosco County Road Commission Overband Crack Fill projects within this bid package will be awarded to single Contractor.

MATERIALS:

All materials in accordance with subsection 502.02 of the Michigan Department of Transportation 2020 Standard Specifications for Construction.

Overband Crack Fill material must be on the current MDOT Approved Qualified Products List.

The Contractor shall provide materials product name, manufactures or suppliers prior to beginning work.

MAINTAINING TRAFFIC & TRAFFIC CONTROL DEVICES:

Traffic will be maintained in accordance with Section 812 of the Michigan Department of Transportation 2020 Standard Specifications for Construction, the MDOT Maintenance Work Zone Traffic Control Guidelines, and current edition of the Michigan Manual of Uniform Traffic Control Devices (MMUTCD). The Contractor shall maintain traffic in one direction and can use lane closures to restrict the flow in one direction of traffic. No lane closures will be allowed after 3:00 P.M. on the day preceding a holiday or holiday weekend. The Contractor shall provide traffic regulators, all signs, and other control devices to maintain traffic as described herein, and to keep traffic off sections being constructed, and to provide for safe travel at all times, or as directed by the Managing Director and or Engineer-Manager.

INSURANCE:

The Contractor shall provide adequate insurance coverage and shall provide the Arenac County Road Commission and Iosco County Road Commission with a certificate of insurance. The contractor shall save harmless the Arenac County Road Commission, Iosco County Road Commission and its Employees against all claims for damages to public or private property and for injuries arising out of, and during, the progress of the work to the completion of the work.

Contractor will meet the requirements set forth in Section 107.10 of the Michigan Department of Transportation 2020 Standard Specifications for Highway Construction.

ROAD COMMISSION CONTACTS:

Any questions about the 2023 Overband Crack Fill Bid for Arenac County Road Commission can be directed to Brad Stauffer, Managing Director at (989) 718-3250 or email Bstauffer@Arenaccrc.org, for Iosco County Road Commission can be directed to Bruce Bolen, Engineer-Manager at (989) 362-4433 or email bolenb@ioscoroads.org.

LOCATIONS FOR ARENAC COUNTY ROAD COMMISSION (\$85,000):

Arenac CRC Group:

Bessinger Road (Santiago Rd to Court Rd) 0.5 miles	_____ /0.5 miles
Grove Road (US-23 to Wyatt Rd) 1.5 miles	_____ /1.5 miles
Grove Road (Sterling Rd to W. Main Street Rd) 5.5 miles	_____ /5.5 miles
Lentner Road (Turner Rd to Dyer Rd) 1.35 miles	_____ /1.35 miles
Lincoln Road (M-61 to Elison Rd) 3.0 miles	_____ /3.0 miles
Pine River Road (City Limits to Arenac State Rd) 2.9 miles	_____ /3.0 miles
S. Main Street Road (Village Limits to Jose Rd) 0.75 miles	_____ /0.75 miles
Santiago Road (Bessinger Rd to Twining Rd) 2.0 miles	_____ /2.0 miles
Walker Road (Jose Rd to W. Main Street Rd) 3.0 miles	_____ /3.0 miles
Hale Road (Stover Rd – US-23) 3.0 miles	_____ /3.0 miles
Stover Road (Arenac State Rd to Hale Rd) 2.65 miles	_____ /2.65 miles
Wyatt Road (M-76 to US-23) 3.75 miles	_____ /3.75 miles
Arenac CRC Group Total:	_____ / 30.0 miles

LOCATIONS FOR IOSCO COUNTY ROAD COMMISSION (\$175,000):

Iosco CRC Group:

Bissonette Road (M-65 to Rea Rd) 13.73 miles	_____ /13.73 miles
Rea Road (Bissonette Rd to F-41) 3.10 miles	_____ /3.10 miles
Rea Road (Bissonette Rd to River Rd) 1.80 miles	_____ /1.80 miles
Cedar Lake Road (Kings Corner Rd to F-41) 5.23 miles	_____ /5.23 miles
Loud Drive (Kings Corner Rd thence South 1.6 miles) 1.60 miles	_____ /1.6 miles

Aulerich Road (US-23 to County Airport) 1.45 miles	_____ /1.45 miles
National City Road (Whittemore Rd thence South 1.47 miles) 1.47 miles	_____ /1.47 miles
Sand Lake Road (0.4 mi North of M-55 to Indian Lake Road) 2.23 miles	_____ /2.23 miles
Indian Lake Road (Sand Lake Rd to Vaughn Rd) 1.62 miles	_____ /1.62 miles
Indian Lake Road (Vaughn Rd to Plank Rd) 1.04 miles	_____ /1.04 miles
Old Stage Road (Sand Lake Rd to M-65) 5.89 miles	_____ /5.89 miles
Old Stage Road (M-65 to Siegrist Rd) 3.92 miles	_____ /3.92 miles
Esmond Road (M-65 to Towerline Rd) 1.0 miles	_____ /1.0 miles
Esmond Road (M-65 to Putnam Rd) 0.95 miles	_____ /0.95 miles
Kokosing Road (South Branch Rd to M-65) 4.29 miles	_____ /4.29 miles
Rollway Road (M-65 to Jose Lake Rd) 3.73 miles	_____ /3.73 miles
Jose Lake Road (Rollway Rd to Chain Lakes Rd) 1.89 miles	_____ /1.89 miles
Chain Lakes Road (Jose Lake Rd to South Branch Rd) 2.47 miles	_____ /2.47 miles
South Branch Road (Chain Lakes Rd to County Line) 2.03 miles	_____ /2.03 miles
South Branch Road (Chain Lakes Rd to Rose City Rd) 4.28 miles	_____ /4.28 miles
Rose City Road (South Branch Rd to County Line) 0.47 miles	_____ /0.47 miles
River Road (Monument Rd to M-65) 3.68 miles	_____ /3.68 miles
River Road (Wilber Rd to Monument Rd) 5.56 miles	_____ /5.56 miles
Monument Road (Wilber Rd to 2 mi South of River Rd) 9.50 miles	_____ /9.50 miles
Wilber Road (M-55 to Miller Rd) 1.01 miles	_____ /1.01 miles
Monument Road (Nunn Rd to Wilber Rd) 1.13 miles	_____ /1.13 miles
Iosco CRC Group Total:	_____ /85.23 miles

**Arenac County Road Commission
And
Iosco County Road Commission**

2023 Overband Crack Fill Fixed Price - Variable Scope Project

TOTAL OVERBAND CRACK FILL COMPLETED MILES

ARENAC COUNTY_____Completed Miles

IOSCO COUNTY_____Completed Miles

TOTAL_____Completed Miles

(COMPANY NAME)

(COMPANY ADDRESS)

(AUTHORIZED SIGNATURE)

(TITLE)

(ADDRESS)

(PHONE)

(FAX)

(EMAIL)